



Calumet Public Schools
Roof and Parking Lot Replacement
Dated April 14, 2011

Addendum #1
1 Page

April 28, 2011

1. **Clarification:** The concrete walk located north of the street shall have a medium broom finish. Contractor shall install a plastic drainage pipe under the walk. Pipe will be supplied by Owner.
2. **Clarification:** Once the contract is awarded, the concrete contractor shall submit a concrete pour schedule to the construction manager. The schedule shall list the number of pours, the approximate concrete quantity for each pour, and the number of working days prior to each pour.
3. **Clarification:** There shall be an expansion joint in the concrete at each outside corner of the existing building.
4. **Clarification:** There shall be a continuous keyway at cold joints located between expansion joints.
5. **Clarification:** Sawn joints shall not exceed twenty feet on center, each way.

End of Addendum #1

ADDENDUM 1-1